

BIHAR STATE POWER TRANSMISSION COMPANY LIMITED

FIELD QUALITY PLAN

Item	Switchyard Civil works	FQP No.	001
Applicability	BSPTCL Projects		
Date of Issue	15.01.2016	REV.	00
Validity	Till next revision		
	·		

TESTS TO BE PERFORMED AT LAB ESTABLISHED BY THE CONTRACTOR AT SITE

Page1 of 1

S. No.	Description of Activity	Items to be Checked	Tests/Checks to be done	Ref. documents	Check/Testing		Counter Checks/Tests by	Accepting
					Agency	Extent	BSPTCL	authority in BSPTCL
1.	Cement Concrete	a) Compressive Strength test	Cube Test	IS: 456	Contractor/BSPTCL Engineer	Minimum 3 samples per 5 cum concrete mix for 7 & 28 days test.	Verification at Random	Engineer-in- charge
		b) Workability	Slump Test	IS: 456	Contractor/BSPTCL Engineer	Day to day work at site	Verification at Random	Engineer-in- charge
2.	Aggregate (Fine & Coarse)	Sieve Analysis	Size of aggregate	IS: 383	Contractor/BSPTCL Engineer	Grading to be done of every lot of aggregate brought at site.	Verification of every lot of aggregate brought at site.	Engineer-in- charge
3	Brick	Compressive Strength Test	Compressive Strength Test	IS: 3495	Contractor/BSPTCL Engineer	Every lot of brick brought at site.	Verification of every lot of brick brought at site.	Engineer-in- charge
		Water Absorption test	Water absorption	IS: 3495	Contractor/BSPTCL Engineer	Every lot of brick brought at site.	Verification of every lot of brick brought at site.	Engineer-in- charge
4	Cement	Consistency Test	Consistency Test	IS: 5513	Contractor/BSPTCL Engineer	Every lot of brick brought at site.	Verification at every lot of cement brought at site.	Engineer-in- charge

General Notes:-

Testing Lab has to be established by the contractor at site shall at least consist of following apparatus /machineries with sufficient number of testing personnels:-

- a. Compressive Strength Testing Machine.
- b. Slump Testing Apparatus.
- c. Aggregate Impact Value (AIV) Testing Apparatus.d. Standard Procter Density Testing Apparatus.
- e. IS Sieve designation as mentioned in annexure- 3 & 4.
- f. Cement Consistency Test Apparatus.