



Bihar State Power Transmission Company Limited, Patna

(Regd. office: Vidyut Bhawan, Bailey Road, Patna)

Contact No : 0612-2504487,7763813835 Fax No: 0612-2504487

TINVAT No. 10011257007 TINCST No. 10011146136 CIN- U40102BR2012SGC018889

email-cecivibspshcl@gmail.com

(Department of civil of BSPTCL)

निम्नांकित कार्यों की मुहरबंद निविदा आमंत्रित की जाती है। निविदा सूचना संख्या:- 69/PR/BSPTCL/2015

कार्यों का विवरण	प्राक्कलित राशि	अग्रधन की राशि	परिमाण विपत्र का मूल्य (नहीं लौटाने योग्य)	कार्य पूरा करने की अवधि
Estimate for the Extension of Control room at 132/33 KV GSS Muzaffarpur.	रु० 8,17,222.00	रु० 16,500.00	रु० 1,250.00	2(Two)

निविदा जमा करने का समय 15.00 बजे तक दिनांक 21.08.2015 एवं निविदा का तकनीकी भाग खुलने का समय उसी दिन 15.30 बजे।

निविदादाता की पात्रता, निविदा से संबंधित कागजात इत्यादि बोर्ड के वेबसाइट <http://bsptcl.in> से डाउनलोड किए जा सकते हैं। डाउनलोड किए गए निविदा कागजात के साथ पात्रता संबंधित कागजात, अग्रधन की राशि एवं परिमाण विपत्र के मूल्य के रूप में कैश/डिमान्ड ड्राफ्ट जो वरीय प्रबंधक (वि० एवं ले०) बिहार स्टेट पावर ट्रांसमिशन कम्पनी लिमिटेड,,पटना को भुगतने हो तकनीकी एवं वाणिज्यकी भाग-1 के साथ संलग्न करना अनिवार्य है अन्यथा निविदायें पूर्णतः रद्द समझी जायेगी। निविदा प्रपत्र अधोहस्ताक्षरी के कार्यालय से निविदा देने की तिथि से एक दिन पूर्व तक अर्थात् दिनांक 20.08.2015 के कार्यालय अवधि तक प्राप्त किया जा सकता है।

मुख्य अभियंता(असैनिक)

भ्रष्टाचार संबंधित शिकायत हेतु, बि०एस०पी०(हो०)कं०लि० विजिलेंस मोबाईल हेल्प लाईन: नं०- 9431821485, 0612-2504969.

उपभोक्ता बिजली बिल सहज वसुधा केन्द्र अथवा <http://bsebbills.org> माध्यम से भी जमा कर सकते हैं।

e-Tendering introduced in BSPHCL for tenders above Rs 10 lacs. For registration log on to www.eproc.bihar.gov.in & contact Helpdesk at 0612-2523006.

बिहार स्टेट पावर ट्रांसमिशन क० लि०, पटना

असैनिक विभाग

निविदा सूचना संख्या-----

Name of work:- Extension of Control room at 132/33 KV GSS at Muzaffarpur.

विशेष शर्त:-

1. निविदा दो भाग में होगा- (क) पार्ट-1- तकनीकी एवं वाणिज्य भाग तथा (ख) पार्ट-2 दर भाग।
2. तकनीकी एवं वाणिज्य भाग में निम्नलिखित कागजात जमा करना होगा:-
(क) अग्रध राशि।
(ख) पूर्व वर्ष का आयकर का बकाया रहित प्रमाण पत्र।
(ग) स्थानीय सेवा शुल्क का प्रमाण पत्र (Local Service Tax)
(घ) आयकर संख्या (पैन)
(ङ) टेका मजदूर प्रमाण पत्र।
3. दर भाग:- In form of above/Below/Estimated.
साथ ही ये भी बतायें कि उक्त राशि का आधार क्या है ?
4. (क) दोनों भाग दो प्रति में मोहर बन्द लिफाफे में जमा करना है।
(ख) एक दर भाग का मोहर बन्द लिफाफे को एक तीसरे बड़े लिफाफे में डाल कर मोहर बन्द कर जमा करना है।
(ग) प्रत्येक लिफाफे के उपर फर्म का नाम एवं पता लिखा होना चाहिए एवं निविदा संख्या ----- भी लिखा होना चाहिए।
(घ) दर भाग के लिफाफा के उपर दर भाग एवं तकनीकी भाग के लिफाफा के उपर तकनीकी भाग लिखा होना चाहिए।
(ङ) दोनों भाग कम्पनी द्वारा निर्धारित फॉर्मेट में भरना होगा।
5. निविदा जमा करने की अंतिम तिथि ----- को अपराह्न 03.00 बजे तक है।
6. निविदा का तकनीकी भाग दिनांक----- को अपराह्न 03.30 बजे निविदाकर्ता या उनके प्राधिकृत प्रतिनिधि के सामने खोला जाएगा।
7. वित्तीय भाग में पथ निर्माण विभाग के पत्र सं०-2046(s) दिनांक-6.3.14के आलोक के आधार पर 10 प्रतिशत से नीचे डाली गई राशि मान्य नहीं होगा।
8. अग्रधन की एवं जमानत की राशि:-
(क) अग्रधन की राशि के रूप में रू०- 16,500.00 जमा करना है।
(ख) अग्रधन राशि राष्ट्रीयकृत बैंक ड्राफ्ट के रूप में वरीय प्रबंधक, वित्त एवं लेखा बिहार स्टेट पावर ट्रांसमिशन कम्पनी लिमिटेड,पटना के पास जमा करना होगा।

(ग) सफल निविदाकर्ता को जमानत राशि जमा करना होगा।

(घ) जमानत की राशि निविदाकर्ता के कुल वार्षिक दर का दस (10) प्रतिशत होगा।

(ङ) जमानत राशि अग्रधन राशि से कम नहीं होगा।

(च) सफल निविदाकर्ता के अग्रधन राशि को जमानत की राशि में समायोजन कर दिया जाएगा एवं शेष बचे राशि को नगद जमा करना होगा।

12 एकरारनामा:-

सफल निविदाकर्ता को 15 दिनों के अन्दर अधोहस्ताक्षरी के साथ एकरारनामा करना होगा।

BIHAR STATE POWER TRANSMISSION COMPANY LIMITED, PATNA
CIVIL DEPARTMENT
VIDYUT BHAWAN, BAILEY ROAD, PATNA

Tender Notice No-----

TECHNICAL PART

TENDER PERFORMA FOR TECHNICAL PART.

- 1 (A) Name of the firm :-
(B) Registered office address :-
(C) Established in Year :-
(D) Name of the top Executive :-
(E) Designation :-
(F) Telephone Numbers :-
(G) Fax Number :-
(H) E-Mail :-
(I) Mobile Number :-

2. Similar nature of work completed in any Public Sector/Private Sector/Govt. Dept.(If Yes, given particulars)
(Attach separate sheet if necessary)

Sl. No.	Name of Department	Name of work	Value of work	Date of completion

3. Registration with statutory bodies. Enclose attested copy of documents in support of this:-

(A) Local Service Tax Number:-

(B) Income Tax Number (PAN):-

(C) Labour License:-

(D) Earnest money:-

Name & Address of The Bank	Bank Draft or Money Receipt No.	Date of issue	Amount

(E) Date of amount paid towards purchase of Tender Document.

Money Receipt Number	Date of issue	Amount

4. Last Income Tax clearance certificate/Return (Enclose copy):-

Year of Assessment	PAN No.	Amount paid to I.T.

5. Acceptance of the terms of payment :-

6. Acceptance of the Technical Requirement :-

7. Acceptance of the penalty clause :-

8. Remarks if any:-

Date-----

Signature of Tenderer with Stamp

Designation-----

Name of the Firm-----

BIHAR STATE POWER TRANSMISSION COMPANY LIMITED, PATNA

1. N.I.T. No. 69 /PR/BSPTCL/2015.
2. Name of Work **Extension of Control room at 132/33 KV GSS at Muzaffarpur.**
3. Estimated Cost Rs.8,17,222.00 only
4. Cost of B.O.Q. Rs.1,250.00 only
5. Earnest Money Rs.16,500.00 only
6. Date & time of receiving tender
7. Date & time of opening tender
8. Duration of work 2 (Month) year

Issued by

Issued to

M.R. No- dated.

BIHAR STATE POWER TRANSMISSION COMPANY LIMITED**PRICE PART-II**

TENDER NOTICE NO.	NIT.No. 69/PR/BSPTCL/2015.
Name of Work	Extension of Control room at 132/33 KV GSS Muzaffarpur.
Estimated Cost	Rs. 8,17,222.00
Cost of B.O.Q.	Rs. 1,250.00
Earnest Money	Rs. 16,500.00
Date & time of receiving tender	21.08.2015 (Upto 3:00PM)
Date & time of opening tender	21.08.2015 (upto 3:30 PM)
Completion time	2(Two) months

BILL OF QUANTITY

Sl.no	Item of work	Quantity	Unit	Rate in Rs./Unit	Rate in words Rs./Unit	Amount
1	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 meters lead: in cement mortar	12.41	Cum	435.70	#NAME?	5407.04
2	Taking out doors, windows and clerestory window shutters(steel or wood) including stacking within 50 meters lead. Of area 3 sqm and below	3	Nos.	30.80	#NAME?	92.40
3	Boring, Providing and installing cast in situ single under reamed piles of specified diameter and length below pile cap in M-25 cement concrete, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring with bentonite solution and the length of the pile to be embedded in pile cap etc. all complete. (Length of pile for payment shall be measured upto to the bottom of pile cap) : 300 mm dia piles	32.93	M	1934.2	#NAME?	63693.21

4	<p>Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically whenever required including cleat angle, Aluminium snap beading for gazing/aneling, C.P. brass/stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge (Glazing, panelling and dash fasteners to be paid for separately): Anodised aluminium (anodised transparent or dyed to required shade according to IS :1868, Minimum anodic coating of grade AC</p>	275	kg	354.8	#NAME?	97570.00
5	<p>Extra for providing heavy sheet glass panes instead of ordinary glass in glazed doors, windows and clerestory window shutters. (Area of opening for glass panes excluding portion inside rebate shall be measured): 13.75 kilograms per square metre (5.5 mm thick) instead of 10 kg/sqm (4.0 mm thick)</p>	22.8	Sqm.	214.1	#NAME?	4881.48
6	<p>Providing and laying position cement concrete of specified grade excluding the cost of centring and shuttering - all work up to plinth level. 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)</p>	5.17	Sqm.	3323.1	#NAME?	17180.43

7	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS :15622 of approved make in all colours and shades ,laid on 20mm thick cement mortar1:4(1 cement 4 coarse sand) including gruting the joint with white cement and matching pigments etc., complete.Size of Tile60x60cm.	55.05	Sqm.	1671.9	#NAME?	92038.1
8	Providing and laying in position specified grade of RCC excluding the cost of centring ,shuttering ,finishing and reinforcement Allwork up to plinth level in 1:1.5:3 with 20mm nominal size	2.21	Cum	3881.2	#NAME?	8577.45
9	RCC work in wall (any thickness),including attached pilasters, buttresses, plinth and string course,fillets ,column,pillars,piers,abutments,posts and struts, etc up to floor five excluding the cost of centring ,shuttering ,finishing and reinforcement in 1:1.5:3with 20mm nominal size	14.56	Cum	4436.6	#NAME?	64596.90
10	Supplying and filling in plinth with local sand and under floors including watering ,ramming consolidating and dressing complete.	31.39	Cum	192.5	#NAME?	6042.57
11	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I	56.79	Sqm.	227.6	#NAME?	12925.40
12	Brick work with bricks of class designation 100A in foundations and plinth in:Cement mortar 1 :4 (1 cement: 4 coarse sand)	20.51	cum	4184	#NAME?	85813.84
a	Extra for Brick work in superstructure above plinth level upto floor V cum	18.69	cum	434.6	#NAME?	8122.67

13 A	Centring and shuttering including strutting,propping etc. and removal of form for. Lintels, beams, plinth bams, griders, bressumers and contilevers.	41.4	Sqm.	251.3	#NAME?	10403.82
13 B	Centring and shuttering including strutting,propping etc. and removal of form for.Columns,Pillars, Piers, Abutments, Posts and Struts	21.37	Sqm.	344.4	#NAME?	7359.83
13 C	Centring and shuttering including strutting,propping etc. and removal of form for. Weather shade,Chajjas, corbels etc. including edges	7.02	Sqm.	385.8	#NAME?	2708.32
13 D	Centring and shuttering including strutting,propping etc. and removal of form for. Suspended floors, roots, landings, balcnies and access platform	56.38	Sqm.	275.6	#NAME?	15538.33
14 A	6 mm cement plaster to ceiling of mix :1:4(1 cement: 4 coarse sand)	58.7	Sqm.	77.4	#NAME?	4543.38
14B	Cement plaster in course sand 12 mm cement plaster of mix: 1:4(1 cement :4 coarse sand)	150.9	Sqm.	100.3	#NAME?	15135.27
14 C	Cement plaster in course sand 15 mm cement plaster on rough side of single or half brick wall of mix. 1:4(1 cement: 4 coarse sand)	103.48	Sqm.	116.3	#NAME?	12034.72
15	Neat cement punning	56.38	Sqm.	27.9	#NAME?	1573.00
16	Extra for providing and mixing water providing materials in cment concrete work in the proportion recommended by the manufactures.	68	per bag (50kg)ce ment	48.07	#NAME?	3268.76

17 A	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade. New work (two or more coats) over and including priming coat with cement primer	127.7	Sqm.	64	#NAME?	8172.80
17 B	Finishing walls with water proofing cement paint of approved brand and manufacture and of required shade to give an even shade New work (three or more coats)	129	Sqm.	60.5	#NAME?	7804.5
18 A	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	127.7	Sqm.	76.8	#NAME?	9807.36
18 B	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	129	Sqm.	76.4	#NAME?	9855.60
19	Providing and fixing on wall face unplasticised-PVC(working pressure 4 kgf per sqm) rain water pipes conforming to IS :4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion.110 mm diameter	10.5	M	214.2	#NAME?	2249.10
20	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.				#NAME?	
21 A	Thermo-Mechanically Treated bars TMTC-500-12mm dia.	800	Kg	71.8	#NAME?	57440.00

21 B	Thermo-Mechanically Treated bars TMTC-500-10mm dia.	390	kg	73.1	#NAME?	28509.00
21C	Thermo-Mechanically Treated bars TMTC-500-8mm dia.	210	kg	74.4	#NAME?	15624.00
21 D	Mild steel 6.0 mm dia	180	kg	70.4	#NAME?	12672.00
22	Carriage of material.				#NAME?	
	A. Local sand(1+2 km)	32.24	cum	233.16	#NAME?	7517.08
	B. Sone sand(86 km)Koilarwar	21.81	Cum	1199.24	#NAME?	26155.42
	C. Stone chips(275 km) Mirza chowki	20.82	cum	3437	#NAME?	71558.34
	D.Briks(1+7 km)	11964	per thou	659.45	#NAME?	7889.66
23	Difference of cost against Gaya zone	172	Cum	417	#NAME?	71724.00
	A.Cement	51.605	Thou	633.18	#NAME?	32675.25
	Brick	29	Cum	233.16	#NAME?	6761.64
24	Deduction of Serviceable bricks	2453	per thou	5023.58	#NAME?	1232284.00
25	Removing mortar from old bricks	4.97	cum	1427.9	#NAME?	7096.66
				Total		817221.84

Say Rs 817222.00

Note :- Quoted rate below 10 % will not be acceptable.

Name of the Contractor	:-	
Address of the Contractor	:-	

<p>I/we offer in Figures..... in words..... % (Percentage) High / Less/Estimated rate as mentioned in the Bill of quantity.</p>	<p>:-</p>	<p>IN FIG.</p>		
	<p>:-</p>	<p>IN WORDS</p>		

Date-----

Signature of Tenderer with Stamp

Designation-----

Name of the Firm-----